

IPC-2222

Sectional Design Standard for Rigid Organic Printed Boards

IPC-2222

February 1998

A standard developed by IPC

The Principles of Standardization

In May 1995 the IPC's Technical Activities Executive Committee adopted Principles of Standardization as a guiding principle of IPC's standardization efforts.

Standards Should:

- Show relationship to Design for Manufacturability (DFM) and Design for the Environment (DFE)
- · Minimize time to market
- Contain simple (simplified) language
- Just include spec information.
- Focus on end product performance.
- Include a feedback system on use and problems for future improvement

Standards Should Not:

- Inhibit innovation
- · Increase time-to-market
- · Keep people out
- · Increase cycle time
- · Tell you how to make something
- Contain anything that cannot be defended with data

Notice

IPC Standards and Publications are designed to serve the public interest through eliminating misunderstandings between manufacturers and purchasers, facilitating interchangeability and improvement of products, and assisting the purchaser in selecting and obtaining with minimum delay the proper product for his particular need. Existence of such Standards and Publications shall not in any respect preclude any member or nonmember of IPC from manufacturing or selling products not conforming to such Standards and Publication, nor shall the existence of such Standards and Publications preclude their voluntary use by those other than IPC members, whether the standard is to be used either domestically or internationally.

Recommended Standards and Publications are adopted by IPC without regard to whether their adoption may involve patents on articles, materials, or processes. By such action, IPC does not assume any liability to any patent owner, nor do they assume any obligation whatever to parties adopting the Recommended Standard or Publication. Users are also wholly responsible for protecting themselves against all claims of liabilities for patent infringement.

IPC Position Statement on Specification Revision Change It is the position of IPC's Technical Activities Executive Committee (TAEC) that the use and implementation of IPC publications is voluntary and is part of a relationship entered into by customer and supplier. When an IPC standard/guideline is updated and a new revision is published, it is the opinion of the TAEC that the use of the new revision as part of an existing relationship is not automatic unless required by the contract. The TAEC recommends the use of the lastest revision.

Adopted October 6, 1998

Why is there a charge for this standard?

Your purchase of this document contributes to the ongoing development of new and updated industry standards. Standards allow manufacturers, customers, and suppliers to understand one another better. Standards allow manufacturers greater efficiencies when they can set up their processes to meet industry standards, allowing them to offer their customers lower costs.

IPC spends hundreds of thousands of dollars annually to support IPC's volunteers in the standards development process. There are many rounds of drafts sent out for review and the committees spend hundreds of hours in review and development. IPC's staff attends and participates in committee activities, typesets and circulates document drafts, and follows all necessary procedures to qualify for ANSI approval.

IPC's membership dues have been kept low in order to allow as many companies as possible to participate. Therefore, the standards revenue is necessary to complement dues revenue. The price schedule offers a 50% discount to IPC members. If your company buys IPC standards, why not take advantage of this and the many other benefits of IPC membership as well? For more information on membership in IPC, please visit www.ipc.org or call 847/790-5372.

Thank you for your continued support.



IPC-2222

Sectional Design Standard for Rigid Organic Printed Boards

Developed by the IPC-D-275 Task Group (D-31b) of the Rigid Printed Board Committee (D-30) of IPC




Users of this standard are encouraged to participate in the development of future revisions.

Contact:

IPC 2215 Sanders Road Northbrook, Illinois 60062-6135 Tel 847 509.9700 Fax 847 509.9798

HIERARCHY OF IPC DESIGN SPECIFICATIONS (2220 SERIES)



FOREWORD

This standard is intended to provide information on the detailed requirements for organic rigid printed board design. All aspects and details of the design requirements are addressed to the extent that they can be applied to the unique requirements of those designs that use organic rigid (reinforced) materials or organic materials in combination with inorganic materials (metal, glass, ceramic, etc.) to provide the structure for manufing and interconnecting electronic, electromechanical, and mechanical components.

The information contained herein is intended to supplement generic engineering considerations and design requirements identified in IPC-2221. When coupled with the engineering design input, the complete disclosure should facilitate the appropriate selection process of the materials and the detailed organic rigid structure fabrication technology necessary to meet the engineering design objectives.

The selected component mounting and interconnecting technology for the printed board should be commensurate with the requirements provided and the specific focus of this sectional document.

IPC's documentation strategy is to provide distinct documents that focus on specific aspect of electronic packaging issues. In this regard document sets are used to provide the total information related to a particular electronic packaging topic. A document set is identified by a four digit number that ends in zero (0).

Included in the set is the generic information which is contained in the first document of the set and identified by the four digit set number. The generic standard is supplemented by one or many sectional documents each of which provide specific focus on one aspect of the topic or the technology selected. The designer of the printed board, needs as a minimum, the generic, the sectional of the chosen technology, the generic engineering considerations, and the engineering description of the final product.

Failure to have all information available prior to starting a design may result in a product that is difficult to manufacture or exceeds the cost predictions or expectations of the printed board.

As technology changes, specific focus standards will be updated, or new focus standards added to the document set. The IPC invites input on the effectiveness of the documentation and encourages user response through completion of "Suggestions for Improvement" forms located at the end of each document

Acknowledgment

Any Standard involving a complex technology draws material from a vast number of sources. While the principal members of the IPC-D-275 Task Group (D-31b) of the Rigid Printed Board Committee (D-30) are shown below, it is not possible to include all of those who assisted in the evolution of this Standard. To each of them, the members of the IPC extend their gratitude.

Rigid	Printed	Board
Comn	nittee	

Chairman Bob Neves Microtek Lab

IPC-D-275 Task Group (D-31b)

Chairman Lionel Fullwood Wong's Kong King Int'l

Technical Liaison of the IPC Board of Directors

Ronald Underwood Circuit Center

IPC-D-275 Task Group

Richard Altenhofen, Motorola GSTG Daniel Arnold, EMD Associates Inc.

Lance A. Auer, Hughes Missile Systems Company

Nanci J. Baggett, Printed Circuit Resources

Steve Bakke, Alliant Techsystems Inc.

Karl J. Bates, Lucent Technologies

Robert E. Beauchamp, Lockheed Martin Missiles & Space

Frank Belisle, Sundstrand Aerospace

David W. Birtle, Raytheon Aircraft Company

Daniel L. Botts, Hughes Training, Inc.

John Bourque, Shure Brothers Inc.

Scott A. Bowles, Sovereign Circuits Inc.

Stephen G. Bradley, CAL Corporation

Jim Brock, SCI Systems Inc.

Ignatius Chong, Celestica

David J. Corbett, DSCC

Brian Crowley, Hewlett Packard Laboratories

Georgia DeGrandis, ABB Ceag Power Supplies Inc.

Yong Deng, Owens-Corning Fiberglass Corp.

Michele J. DiFranza, The Mitre Corp.

C. Don. Dupriest, Lockheed Martin Vought Systems

Theodore Edwards, Honeywell Inc.

Will J. Edwards, Luceut Technologies Inc.

Werner Engelmaier, Engelmaier Associates, Inc.

Thomas R. Etheridge, McDonnell Douglas Aerospace Joe Fielstad, Tessera Inc.

Martin G. Freedman, Amp Inc.

Lionel Fullwood, Wong's Kong King Int'l

Mahendra S. Gandhi, Hughes Aircraft Co.

Paul Grande, Jr., U.S. Navy

Michael R. Green, Lockheed Martin Missiles & Space

Lyle F. Harford, Texas Instruments Inc.

Andrew J. Heidelberg, Micron Custom Mfg. Services Inc.

Ralph J. Hersey, Ralph Hersey & Associates

Phillip E. Hinton, Hinton -PWB-Engineering

Octavian Iordache, Circo Craft Co. Inc.

Don Jensen, Endicott Research Group

Arturo J. Jordan, Pollak Trnsprtam Electrnics Div

John A. Kelly, Motorola GSTG

Therese Kokocinski, Northrop Grumman Corporation

Stephen Korchynsky, Luckheed Martin Federal Systems

George T. Kotecki, Northrop Grumman Corporation

Thomas E. Kurtz, Hughes Defense Communications

Clifford H. Lamson, Harris Corp.

Bonnie Lauch, Honeywell Inc.

Stan C. Mackgum, Eriesson Inc.

James F. Maguire, Boeing Defense & Space Group

David J. Malanchuk, Eastman Kodak Co. KAD

Wesley R. Malewicz, Siemens Medical Systems Inc. Susan Mansilla, Robisan Laboratory Inc.

Lester Mielczarek, CAE Electronics Ltd.

Kelty J. Miller, CAE Electronics Ltd.

John H. Morton, Lockheed Martin Federal Systems

Karl B. Mueller, Hughes Aircraft Co.

Joseph L. Mulcahy, Methode Electronics Inc. East

Benny Nilsson, Ericsson Telecom AB

R. Bruce. Officer, Sanders, A Lockheed Martin Co.

Scott S. Opperhauser, Trace Laboratories - East

John Papinko, Gulton Data Systems

Ron Payne, Primex Aerospace

Richard Peyton, Lockheed Martin Astronautics

Larry L. Puckett, Sandia National Labs Albuquerque

Paul J. Quinn, Lockheed Martin Missiles & Space

Kurt Ravenfeld, Lockheed Martin Corporation

Randy R. Reed, Merix Corporation

Bruce C. Rietdorf, Hughes Defense Communications

Jerald G. Rosser, Hughes Missile Systems Company

Vincent J. Ruggeri, Raytheon Company

Don W. Rumps, Lucent Technologies Inc.

Robert Russell, Texas Instruments Inc.

Merlyn L. Seltzer, Hughes Delco Systems Operations

Nusrat Sherali, IBM Corp.

Lowell Sherman, DSCC

Rae Shyne, Prototron Circuits Inc.

Grant (Rick) W. Smedley, III, Printed Circuit Resources

E. Lon, Smith, Lucent Technologies Inc.

Joseph J. Sniezek, IBM Corp./ Endicott Electronic Pa

William F. Spurny, AlliedSignal Aerospace

Robert J. St. Pierre, New England Laminates Thomas K. Stewart, Speedy Circuits

Gil Thomax, Honeywell Inc.

Ronald E. Thompson, U.S. Navy

Max E. Thorson, Compaq Computer Corporation

Lutz E. Treutler, Fachverband Elektronik Design

Robert Vanech, Northrop Grumman Norden Systems Eric L. Vollmar, Methode Electronics Inc.

Forrest L. Voss, Rockwell International

Rich Warzecha, Advanced Flex Inc.

Clark F. Webster, Computing Devices International

David A. White, Input/Output Inc.

Table of Contents

1.0	SCOPE	1	7.0	THERMAL MANAGEMENT 16
1.1	Purpose	1	8.0	COMPONENT AND ASSEMBLY ISSUES 16
1.2	Document Hierarchy	1	8.1	General Attachment Requirements
1.3	Presentation		8.1.1	Anachment of Wires/Leads to Terminals 16
1.4	Interpretation	1	8.1.2	Board Extractors
1.5	Classification of Products	Linn		
1.5.1	Board Type	1	9.0	HOLE/INTERCONNECTIONS 16
1.6	Assembly Types		9.1	General Requirements for Lands with Holes 16
-	APPLICABLE DOCUMENTS		9.1.1	Land Requirements
2.1		10103	9.1.2	Thermal Relief in Conductor Planes 16
2,1	Institute for Interconnecting and Packaging Electronic Circuits (IPC)	1	9.1.3	Clearance Area in Planes 17
2.2	Underwriters Laboratories		9.1.4	Nonfunctional Lands
20.00			9.1.5	Conductive Pattern Feature Location
3.0	GENERAL REQUIREMENTS	3		Tolerance
3.1	Performance Requirements	3	9.2	Holes 18
4.0	MATERIALS	3	9.2.1	Unsupported Holes
4.1	Material Selection		9.2.2	Plated-Through Holes 19
4.2	Dielectric Base Materials (Including		9.2.3	Etchback 15
7.2	Prepregs and Adhesives)	3	9.3	Drill Size Recommendations for
4.2.1	Epoxy Laminates			Printed Boards
4.2.2			10.0	GENERAL CIRCUIT FEATURE
4.2.3			10.0	REQUIREMENTS
4.2.4	•			
4.3	Laminate Materials		MOE	
4.3.1			10.1	Conductor Characteristics
4.3.2			10,1,1	Edge Spacing 20
4.3.3			10.1.2	Balanced Conductors 21
4.3.4			10.1.3	
4.3.5				Contacts
	Angle Com Commission		10.1.4	Metallic Finishes for Flush Conductors 21
4.3.6			10.2	Land Characteristics 21
4.3.7	Laminate Material		10.2.1	Lands for Interfacial Connection Vias 21
4.4	Conductive Materials		10.2.2	Offset Lands
4.5	Organic Protective Coatings	13	10.2.3	Conductive Pattern Feature Location
4.6	Markings and Legends	13		Tolerance
8.0	MECHANICAL/PHYSICAL PROPERTIES	13	10.2.4	Nonfunctional Lands
5.1	Fabrication Requirements		10.3	Large Conductive Areas 21
5.2	Product/Board Configuration		44.0	DOGUMENTATION
			11.0	DOCUMENTATION
5.2.1	Board Geometries		11.1	Filled Holes
5.2.2	The state of the s		11.2	Nonfunctional Holes
5.3	Assembly Requirements		12.0	QUALITY ASSURANCE22
5.3.1	Assembly and Test	14		
5.4	Dimensioning Systems	15		
5.4.1	Grid Systems	15		Figures
5.4.2	Profiles, Cutouts and Notches	15	Figure	
6.0	ELECTRICAL PROPERTIES	14		
0.0	ELECTRICAL PROPERTIES	10	Figure	- Libraria ayer mickness measurement

Figure 4-2	Designer / end user materials selection map	Table 4-5	BT Copper Clad Laminate Construction Selection Guide
Figure 5-1 Figure 5-2	Panel borders	Table 4-6	Polyimide Copper Clad Laminate Construction Selection Guide
Figure 5-3	Breakaway tabs15	Table 5-1	Panel Size to Manufacturing Operation Relationships
Figure 8-1	Permanent board extractor	Table 5-2	Standard Scoring Parameters
Figure 8-2 Figure 9-1	External board extractor	Table 5-3	Tolerance of Profiles, Cutouts, Notches, and Keying Slots, as Machined, mm
Figure 9-2 Figure 9-3	Foil web size	Table 9-1	Feature Location Tolerances (Lands, Conductor Pattern, etc.) (Diameter True Position)
Figure 10-1 <i>A</i> Figure 10-18 Figure 10-2	••	Table 9-2	Minimum Unsupported Holes Tolerance Range (Difference between high and low hole size limits)
	with isothermal conductors	Table 9-3	Plated-Through Hole Diameter to Lead Diameter Relationships
	Tables	Table 9-4 Table 9-5	Plated-Through Hole Aspect Ratio
	Clad Laminate Maximum Operating Temperatures	1000 0.0	Tolerance Range, mm (Difference between high and low hole
	FR-4 Copper Clad Laminate Construction Selection Guide	Table Pil	size limits)
Table 4-3	High T _G FR-4 Copper Clad Laminate Construction Selection Guide	Table 9-7	Hole Vias
Table 4-4	Cyanate Ester (170 to 250° T _G) Copper Clad Laminate Construction Selection Guide 8	Table 10-1	Maximum Board Thickness

Sectional Design Standard for Rigid Organic Printed Boards

1.0 SCOPE

This standard establishes the specific requirements for the design of rigid organic printed boards and other forms of component mounting and interconnecting structures. The organic materials may be homogeneous, reinforced, or used in combination with inorganic materials; the interconnections may be single, double, or multilayered.

1.1 Purpose The requirements contained herein are intended to establish specific design details that shall be used in conjunction with IPC-2221 (see 2.0) to produce detailed designs intended to mount and attach passive and active components.

The components may be through-hole, surface mount, fine pitch, ultra-fine pitch, array mounting or unpackaged bare die. The materials may be any combination able to perform the physical, thermal, environmental, and electronic function.

- 1.2 Document Hierarchy Document hierarchy shall be in accordance with the generic standard IPC-2221.
- 1.3 Presentation Presentation shall be in accordance with the generic standard IPC-2221.
- 1.4 Interpretation Interpretation shall be in accordance with the generic standard IPC-2221.
- 1.6 Classification of Products Classification of Products shall be in accordance with the generic standard IPC-2221 and as follows:
- 1.5.1 Board Type This standard provides design information for different board types. Board types are classified as:
- Type 1 Single-Sided Printed Board
- Type 2 Double-Sided Printed Board
- Type 3 Multilayer Board without Blind or Buried Vias
- Type 4 Multilayer Board with Blind and/or Buried Vias
- Type 5 Multilayer Metal-Core Board without Blind or Buried Vias
- Type 6 Multilayer Metal-Core Board with Blind and/or Buried Vias
- 1.6 Assembly Types A type designation signifies further sophistication describing whether components are mounted

on one or both sides of the packaging and interconnecting structure. Type 1 defines an assembly that has components mounted on only one side; Type 2 is an assembly with components on both sides. Type 2, Class A is not recommended.

Figure 1-1 shows the relationship of two types of assemblies.

The need to apply certain design concepts should depend on the complexity and precision required to produce a particular land pattern or P&I structure. Any design class may be applied to any of the end-product equipment categories; therefore, a moderate complexity (Type 1B) would define components mounted on one side (all surface mounted) and when used in a Class 2 product (dedicated service electronics) is referred to as Type 1B, Class 2. The product described as a Type 1B, Class 2 might be used in any of the end-use applications; the selection of class being dependent on the requirements of the customers using the application.

2.0 APPLICABLE DOCUMENTS

The following documents form a part of this document to the extent specified herein. If a conflict of requirements exist between IPC-2222 and those listed below, IPC-2222 takes precedence.

The revision of the document in effect at the time of solicitation shall take precedence.

2.1 Institute for Interconnecting and Packaging Electronic Circuits (IPC)1

IPC-EG-140 Specification For Finished Fabric Woven From "E" Glass for Printed Board

IPC-MF-180 Metal Foil for Printed Wiring Applications

IPC-CF-152 Composite Metallic Materials Specification for Printed Wiring Boards

IPC-D-279 Design Guidelines for Reliable Surface Mount Technology Printed Board Assemblies

IPC-TM-650 Test Methods Manual²

Method 2.1.1 Microsectioning

Method 2.1.6 Thickness of Glass Fabric

IPC-SM-782 Surface Mount Design and Land Pattern Standard

^{1.} IPC, 2215 Sanders Road, Northbrook, IL 60062

^{2.} Current and revised IPC Test Methods are available through IPC-TM-650 subscription and on the IPC Web site (www.ipc.org/html/lestmethods.htm).




Figure 1-1 Electrical assembly types

IPC-2221 Generic Standard on Printed Board Design

IPC-4101 Laminate/Prepreg Materials Standard for Printed Boards

IPC-6012 Qualification and Performance Specification for Rigid Printed Boards

2.2 Underwriters Laboratories³

UL 746E Standard Polymeric Materials, Materials Used in Printed Wiring Boards

3.0 GENERAL REQUIREMENTS

General requirements shall be in accordance with the generic standards IPC-2221

3.1 Performance Requirements Finished rigid printed boards shall meet the performance requirements of IPC-60.2.

4.0 MATERIALS

- 4.1 Material Selection Material Selection shall be in accordance with the generic standard IPC-2221
- 4.2 Dielectric Base Materials (including Prepregs and Adhesives) Dielectric base materials shall be in accordance with the generic standard IPC-2221 and the following
- **4.2.1 Epoxy Laminates** Epoxies are the most common resin materials which are combined with glass cloth to produce laminates. When compared to other laminate materials, epoxies offer advantages in availability and relative case in processing. The many different types and blends of epoxies exhibit a wide range of selection for usage or soldering processes; epoxies with a T_g (glass transition temperature) from 110 to 120°C up to 180 to 190°C are available from most laminate suppliers with some of the most used in the 135 to 145°C range.
- 4.2.2 High-Temperature Laminates High temperature aminates include those made from resins such as Epoxy, Cyanate Ester, Triazine blends and polyimide. High temperature resin laminates offer the advantages of increased chemical and temperature resistance. Disadvantages include the need for specialized processing and higher materia, cost.
- 4.2.3 Special Clad Materials The use of surface mount technology may require the use of special clad materials when coefficient of thermal expansion matching is critical. Examples of these special materials are copper-clad Invar.

- epoxy or polyimide with aramid fiber and polyimide/ quartz. The most common usage is for Class 3 boards, although there may also be some application for Class 2. These materials offer the advantages of performance for specialized applications, the need for unique processing during board fabrication is a disadvantage
- 4.2.4 Other Laminates Laminates, such as paper-based phenolics etc., have acceptance in some consumer products where the complexity is quite low due to lesser materia, and manufacturing costs. These materials are associated with very high volume products with lower performance requirements than those usually associated with epoxy type laminates.
- 4.3 Leminate Materials Laminate materials shall be in accordance with the generic standard IPC-2221 and as follows.

When metal clad, foil type shall be as specified in IPC-MF-150. Unclad laminates without an adhesive, per IPC-4101 may be used as fillers in multilayer boards for dielectric spacing between layers

When Underwriter's Labs (UL) requirements are imposed, the material used must be approved by UL for use as fillers in multilayer boards for dielectric spacing between layers. Printed boards shall be fabricated from the laminate materials specified in Table 4-1 or UL 746E.

The board design shall be such that internal temperature rise due to current flow in the conductor, when added to all other sources of heat at the conductor/laminate interface. will not result in an operating temperature in excess of that specified for the laminate material. The values in Table 4-1 are based on long term thermal aging tests by UL and may be mandatory for designs to be used in UL approved prodocts. Since heat dissipated by parts mounted on the boards will contribute local heating effects, the material selection shall take this factor, plus the equipment's general internal rise temperature, plus the specified operating ambient temperature for the equipment into account. Hot spot temperatures shall not exceed the temperatures specified in Table 4-1 for the laminate material selected. Materials used (copper-clad, prepreg, copper foil, heat sink, etc.) shall be specified on the master drawing.

4.3.1 Measurement of Dielectric Thickness Dielectric thickness will vary across applications. Thickness by mechanical measurement is determined in accordance with IPC-TM-650, Method 2.1.6. Thickness by microsection (view shown in Figure 4-1) is determined in accordance with IPC-TM 650, Method 2.1.1 The dielectric thickness is measured in accordance with Figure 4-1 and taken at the closest point between metal claddings.

³ Underwriter s Labe, 333 Pfingsten Avenue, Northbrook, IL 60062

Table 4-1 Clad Laminate Maximum Operating Temperatures¹

	Designation	Dielectric	Temperature ^{4, 5, 6, 7}
NEMA	IPC-4101	Thickness (min)	(max)
FR-4	21/24/25/27	0.1 mm	120°C
		D.4 mm	130°C
FR-5	23	0.6 mm	140°C
1		1 4 mm	170°C
GPY	40/41/42	0.1 mm	140°C
		1 6 mm	170°C
	50/52	0.1 mm	120°C
		0.4 mm	130°C
	51/53/60	0.1 mm	140°C
		1.6 mm	170°C
	30/26	0.1 mm	120°C
1		0.4 mm	130°C
	70/71	0.1 mm	140°C
		0.4 mm	170°C

- Ambient temperature plus the temperature rise caused by current in the conductors and components.
- 2 FR-4 reministes should not be combined its one board with GPY proprogs.
- 3. When GPV taminates are combined in one board with FR-4 prepriets, the temperature shall be that specified for the FR-4 materials
- 4. A multilayer board shall be limited to a maximum operating temperature for the total dielectric studioss shown above
- For reinforcement/resin combinations not specifically shown above, the maximum operating temperature should be close to that of a flated combination with the same resin
- 5. Other materials in the same classification with higher operating temperatures may be available
- 7 Distactric trickness smaller than those shown above may be temperature raised by UL for certain taminate manufacturers

4.3.2 Dielectric Thickness/Spacing The minimum dielectric thickness/spacing shall be specified on the master drawing. If the minimum dielectric spacing and the number of reinforcing layers are not specified, the minimum dielectric spacing is 0.09 mm and the number of reinforcing layers may be selected by the supplier.

Note: Minimum dielectric spacing may be specified to be 0.03 mm; however, low-profile copper foils should be used and the voltages employed should be taken into consideration so as not to cause breakdown between layers. See IPC-2221 for more information on electrical conductor spacing.




Figure 4-1 Dielectric layer thickness measurement

4.3.3 Laminate Properties

- **4.3.3.1 Thickness Toterance** When specifying overall multilayer board thickness, and individual dielectric thickness between layers, it is important to recognize the effects of accumulated tolerances of individual dielectrics on the overall thickness of completed boards.
- 4.3.3.2 Resin Content Laminates are a composite of resin and glass cloth or other reinforcement. As laminate thicknesses increase, heavier glass cloths or reinforcements are used, and the percentages of resin (resin content) decrease. Laminates with higher resin content tend to have higher coefficients of thermal expansion and lower dimensional stability. However, if resin contents are too low, weave exposure and measing may result. The glass to resin ratio of a laminate also has a direct effect on dielectric constant.

4.3.4 Propreg

- **4.3.4.1** Epoxy Low T_g epoxies are the most common resin materials which are combined with glass cloth or other reinforcement and semi-cured to produce prepregs. Epoxy prepregs will produce acceptable product for Class 1, 2, and 3 multilayer printed boards. Because of different chemical processing requirements for various resin systems, it is preferred to use like resins for laminates and prepregs when constructing a multilayer printed board.
- **4.3.4.2 High-Temparature Prepregs** High temperature prepregs include those made from resins such as Epoxy, Cyanate ester, Triazine blends and polyimide. High temperature prepregs may be used for specialized Class 2 multilayer printed board applications, but are more commonly used for Class 3 multilayer printed boards.
- **4.3.4.3 Glass Style** A variety of glass cloth styles are available for prepregs (see IPC-EG-140). The glass cloth selection is dependent upon dielectric thickness and tolerance required, circuit filling needs, and electrical requirements of the dielectric.
- 4.3.4.4 Electrical Requirements For multi-ayer printed boards which have controlled impedance requirements, the dielectric constant of the laminated prepring must be controlled Because dielectric constant is a function of the resin/glass or other reinforcement ratio, prepring styles should be chosen so that after lamination, the proper retained resin content is achieved in order to arrive at the specified dielectric constant.
- **4.3.5 Single-Clad Laminates** Laminates with foil on one side may be used as an outer layer or internal layer of a multilayer printed board, as appropriate.

- 4.3.6 Double-Clad Laminates Laminates with foil on both sides may be used to provide either internal or external conductive layers. Double-clad laminate is specified in both industry and IPC specifications by the dielectric separation between the conductive layers as shown in Figure 4-1. Tables 4-2 through 4-6 provide information on the properties of finished bare laminates for different prepreg constructions. To establish final laminate thickness with copper, add 35 µm for each oz. of copper on the laminate
- **4.3.7 Laminate Material** Laminate materials shall be specified on the drawing. See Figure 4-2 for a mapping of the recommended material selection process.

Materials are generally purchased to meet the requirements of IPC-4101. A typical material code designation of a specific material would be L21 1500 CI/CI A1A. When the finished product requires Underwriters Labs (UL) approval, material shall be ordered to meet UL specifications.

- **4.3 7.1 Typical Material Designation** The first three characters of the code designate the type of material "L" indicates laminate material, "P" indicates prepring material.
- "L21"— Woven "E" glass fabric impregnated with flame resistant, epoxy resin of a type that is a majority of d functional resin. Small amounts of multifunctional resin or novalacs are sometimes added to enhance the physical properties. This is the standard NEMA FR-4 grade manufactured by most laminators since the 1950s. The glass transition temperature (T₀) is normally from 110 to 150°C but not specified.
- "L25"— Woven "E" glass fabric impregnated with flame resistant epoxy resin which is commonly a polyfunctional type resin. This resin may be modified with other epoxies to increase the high temperature physical properties. This material may be used where repeated soldering operations to replace components are anticipated. The T_a is specified to be from 150 to 200°C.
- "L26"— This grade is similar to L25 except that the epoxy resin is modified with non-epoxy resins such as cyanate esters and/or bismalcum.des. The uses are similar but where higher temperatures may be anneipated. The T_g is specified to be from 170 to 220°C.
- "L40" Woven "E" glass fabric impregnated with polyimide resin. Introduced in the 1960s for high temperature operating environments such as missile engine controls, the resin has been supplied primarily from one European source. The natural color is opaque brown. The T_g is normally from 200 to 250° but not specified.
- "L42"— This grade is similar to L40 except that the polyimide resin may be modified with nonpolyimide resins. The primary purpose of the modifications are to improve the producibility of the printed board. The applications are similar. The T_g is specified as from 200 to 250°C.

REG# THICKNESS FR-4 GD 0.05mm	-					-						-			
	NESS	CONSTRUCTION	% BC	ž	DY TO	S	Z CITE	Z Z	CHEM	CHEM MEASLE	AVAL	CDST	FLAT SM	SMOOTH DE	DAIL
	C E	108	2	404	0	0	0	0	•	•	0	0			+
FR-4 01 0.07mm	E	1080	2	4.25	•	•	0	0	•	•	0	•			+
FR-4 02 0.08mm	MITT	21106	I	4,10	•	0	0	•	0	0	0	0		+	+
FR-403 0.11mm	E CIE	2x106	11	4.10	•	0	0	•	0	0	0	0			+
FR-4 04 D-11mm	ШШ	2113	6	4,50	•	0	•	•	0	0	0	•			÷
FR-4 06 0 14mm	E E	106/2113	:	4.34	•	•	•	•	•	0	0	0	ı		Ļ
FR-4 06 D 13mm	mm	2xt080	2	4.26	0	0	•	0	0	•	•	•		+	+
FR-4 07 D.13mm	IHEN	2516	÷	4,48	0	0	•	0	0	0	0	•			
FR-4 08 D.18mm	Hath	108/2118	5	4.46	•	•	0	•	0	0	•	0	ı		
FR-4 09 0 18mm	men	1080/2113	I	4,4	•	0	0	•	0	0	•	0	ı		1
FR-4 10 0.18mm	THE THE	2x2113	9	4.60	0	0	0	Ð	•	0	0	0			_
FR-4 91 0.18mm	-	7428	9	4.36	0	0	•	0	0	0	0	•		ı	1
FR-4 12 0.21mm	E E	2113/2114	오	4.60	•	•	0	0	0	0	•	0	ı		
FR-4 15 0.21mm	TH.TH	2x2116	Ç	4.65	•	0	0	0	0	0	0	0	+		
FR-4 14 0.25mm	日子	2x2116	=	4.4	•	0	0	0	•	•	0	0	+		
FR-4 16 D.28mm	mm	7628/1080	Ç	4,0	•	•	•	0	0	0	0	•	1		
FR-4 16 0.28mm	E	2x1080/2118	=	4.0	•	0	0	•	•	•	0	0	+	+	
FR-4 17 D.51mm	thirth.	2×108D/762B	Ç	17	•	•	Ð	•	٠	٠	•	0	+	+	ļ,
FR-4 18 0.32mm	E	7028/2110	4	4.0	•	•	•	•	0	0	0	•	1	1	
FR-4 19 0.37mm	E E	2x762B	÷	4.7	•	•	٥	•	•	0	0	•	+	ı	,
FR-4 20 0.37mm	mm.	2×2111/7628	*	4.0	•	•	•	•	•	•	•	0	+		1
FR-4 21 0.43mm	E E	2x2116/7628	*	4.6	0	•	0	•	0	0	0	0			ļ,
FR-4 22 0.43mm	C E	2×7628/1090	7	43	•	•	0	0	•	0	•	•	+	ı	ı
FR-4 23 0.48mm	mm	2x7625/2115	7	3	•	0	•	0	0	0	•	Ф	4	I	1
FR-4 24 0.81mm	min	2H1080/2k7628	Ŧ	4	•	•	0	٥	•	•	0	0	4	+	ı
FR-4 26 0.85mm	EE	3×7624	2	43	•	0	9	•	0	•	•	•	+		1
FH-4 28 0.64mm	mm	ZKZ176/2K7628	47	4.8	•	•	0	0	0	0	•	0	·+		ı
FR-4 27 0.51mm	mm.	3x7828/1090	7	43	•	0	9	o	•	0	•	•	ı	ı	1
FR.4.28 0.74mm	HE.	4x7628	43	43	•	•	•	0	0	0	•	0	4	Į	,
FR-4 29 0.74mm	EE	ZKZ113/3x7628	#	4/3	•	•	0	0	0	0	0	0	+		ı
FR-4 30 0.75mm	rhim	4x7828/1080	ā	4.7	0	0	0	0	0	•	•	0	+	ı	
FR-4 3* 1.52mm	EE	8x7524	7	47	•	0	0	0	0	0	0	•	+	1	,

Table 4-2 FH-4 Copper Clad Laminate Construction Selection Guide

HIGH TG FR-4 COPPER CLAD LAMINATE CONSTRUCTION SELECTION	MEASLE AVAIL COST FLAT SMOOTH DRILL	0	+	+	+	•	+	+	•	- 0	I 0	0	1	E 0	+ 0	+	 	+	+ + •	0	+ •	+	0	+ •	+	+ 0	+ 0 0	+	1 0	+	+ 0	+	0
NSTRU	CHEM																														•		
ie Cor	Z CTE THICK TOL																														0		
IA	50	0	0	0	•	0	•	8	0	•	0	0	0	0	0	0	9		•	0	•	•	•	0	•	•	•	•	•	•	•	•	•
AMI	DK. TOL.	0	€	•	•	•	•	0	0	•	•	0	0	•	•	0	9	•	•	•	0	•	•	•	•	•	•	•	•	•	•	•	•
AD	ă	80'W	428	4.16	4.10	4.30	A.30	17	0.40	446	4.40	979	4.71	9	441	4	3	3	5	9.9	¥.	4.0	4.6	4.3	479	4.6	40	4.8	4.7	63	4.2	4.7	2
R CL	% RC	2	8	1	21	ž	3	I	2	2	Ξ	3	\$	=	4	==	4	=	7	43	ş	#	#	4	41	2	9	29	2	ŧ	2	眷	#
R-4 COPPE	CONSTRUCTION	108	1010	Zk10B	2×104	2113	106/2113	241060	2115	106/2116	1080/2113	2x2113	7528	2113/2118	2×2118	3×2110	7828/1080	2x1D80/2116	2×1080/7628	7628/2116	2×7628	2x2113/7628	2x2118/7628	2×7828/1080	2x7428/2114	2x1080/2x7628	3,711.28	2x2116/2x762b	3x7628/1080	4x7628	2x2113/3x7628	4x7628/1080	Bx762B
HIGH TG F	THICKNESS	0.08mm	0.07ஈா	0.0Bestriti	0.11mm	0.11444	0.14mm	0.13mm	D.13mm	D.14mm	0.10mm	0.18mm	0.18mm	D.21mm	0.21mm	0.25mm	0.26mm	0.26mm	0.31mm	0.32тт	0.37mm	0.37mm	0.43mm	0.43mm	0.45mmin	0.54 mm	0.53mm	D.64mm	D.61mm	0.74mm	0.74mm	0.75mm	1.52mm
	REGS	HFR-4 00	HFR-4 01	HFR-4 02	HFR-4 03	HFR-4 04	HFR-4 08	HFR-4 08	HFR-4 07	HFR-4 04	HFR-4 00	HFR-4 10	HFR-4 11	HFR-4 12	HFR-4 13	HPR-4 14	HFR-4 13	HFR-4 10	TFR-4 17	HFR-4 18	HFR- 10	HFB-4 20	HFR-4.21	HFR-4 22	HFR-4 23	HFR-4 24	HFR-4 28	HFR-4 28	HFR-4 27	HFR:4 28	HFR-4 29	HFR-4 30	HFR-4 31

Table 4-3 High T_a FR-4 Copper Clad Laminate Construction Selection Guide

ğ	T)WC	+	+	+	+	+	+	+			ı	+	ı			þ			ı	1	ı	ı	ı	1	1	ι	ı	ı	Ĭ	ı	ŧ	ŧ	ı		
CONSTRUCTION SELECTION GUIDE	SMOOTH DRILL	+	+	+	+		+	+					1				ı	+	+	ı	ı			1	ş	+	ı			1		[ι		
OT:0	FLAT SI						1			ı	1			ı	+	+	ı	+	+	1	+	+		+	+	+	+	+	I	÷	+	+	+		
ie E	COST	0		Ó	0		0	mD.		0	٥	0	•	0	٥	ın.			0			0	0	•	•	Ó		0	•		0	•			
SNO						_		Ĭ					_	_	Ĭ	_																	_		
)CT	E AVAIL	0	0	9	Ó	0	•	•	0	•	•	O	O	•	•	•	⊕	٥	•	Q	•	(JP	0	•	•	0	•	€D	•	•	0	•	9		
STR	MEASLE	•	•	•	•	0	0	•	0	0	0	0	0	0	o	0	0	٠	•	0	0	•	•	0	0	•	•	•	0	O	•	•	0		
S	CHEM	•	•	•	0	0	€	•	0	0	0	0	•	0	0	Ф	•	•	•	0	•	•	0	•	0	•	9	P	•	Ó	•	0	0		
	The CX	0	0	•	0	•	•	Q	0	•	0	0	•	•	•	0	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	0		04,300
AMIN	I CTE	0	0	0	0	•	Ð	Œ	•	0	٥	o	0	0	0	0	•	0	0	•	•	•	•	•	•	Ф	•	0	•	•	0	0	0	•	
70	g	0	•	0	•	0	•	•	0	•	0	0	0	•	0	0	•	0	•	0	•	•	•	•	•	•	•	•	•	•	•	•	•	0	1
~ C □	0K. TOL.	0	•	0	0	0	•	0	0	•	0	0	0	•	•	0	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	
13dd	¥	3.10	1.17	3,44	128	3.70	3,77	3.48	3,71	1.10	3,80	3.78	1.00	3.46	3.80	1.71	3.63	3.70	1,10	1.60	4.15	3.80	1.90	4.11	4.11	4.85	4.15	1.90	4.05	4.15	100	4.15	4.04	•	Bether +
<u>ဒ</u>	28.5	ř	62 3.				52 3.	**	15 3.			* 9	Ť	-																					-
° TG	μ	F		9	2	2	-	-	*	2	<u></u>	-	4	4	-	24	45	2	45	4	8	Ŧ	3	#		¥	7	\$	두	#	¥	Ħ	\$		
CVANATE ESTER (170 to 230° TG) COPPER CLAD LAMINATE	CONSTRUCTION	188	1000	2×106	2×104	2113	106/2/13	241080	ZIM	106/2/18	1000/2113	2113	7628	\$113/2198	212110	242110	7828/1080	Zh1080/2118	Z=1080/762E	7522/2118	217028	2x2113/7428	2,2116/7428	297628/1000	2x7628/2116	2x1080/2x7428	3x7628	22216/217628	3×7626/1080	4x7628	212117117128	4x7526/1000	8x7528		
NATE ESTER	THICKNESS	0.05mm	Ф.07mm	0.08ார	0.11mm	Outime	0.14mm	0.13mm	O.13mm	0.16mm	D.16mm	0.18mm	0.18mm	0.21mm	0.21mm	O.28mm	0.26ாா	0.28mm	0.31mm	0.32mm	0.37mm	0.37mm	0.43mm	€.43mm	0.48ார	4.51mm	0.83mm	0.04mm	0.61mm	0.74mm	6.74mm	0.7\$mm	1.52mm		
CYAN	REG#	OE 00	CE 04	CE 03	CE 03	CE 04	0E 06	90 30	CE 07	00 30	CE OB	CE 10	CE 11	CE 12	GE 13	CE 14	CE 18	CE 18	CE 17	GE 18	CE 19	CE 20	CE 21	CE 22	CE 23	CE 24	CE 26	CE 24	CE 27	CE SI	CE 29	GE 30	CE 31		

Table 4-4 Cyanate Ester (170 to 250° T_G) Copper Clad Laminate Construction Selection Guide




Table 4-5 BT Copper Clad Laminate Construction Selection Guide

FOLY	MIDE (POLYIMIDE COPPER CLAD	LAN	ANIE	LAMINATE CONSTRUCTION SELECTION GUIDE	Š	STR	UCTI	NO	SELE	CTIC	N G	Ü	ш	
REG#	THICKNESS	CONSTRUCTION	% BC)Wd	DK. TOL.	50	2 CTE	10 T	CHEM	MEASLE	AVAIL	TSOO	PLAT	ВМОПТН	DRILL
POLY 00	0.05mm	106	PA.	4.00	0	0	0	0	•	•	0	•		+	+
POLY 01	D.07mm	1090	2	4.02	•	0	0	0	0	•	C	q		+	+
POLY 02	0.04mm	2x108	÷	4.05	•	0	Q	9	•	•	0	0		+	+
POLY 03	0.11mm	2x108	=	3.80	0	•	0	•	0	•	c	C		+	+
POLY 04	D,11mm	2113	65	4.21	•	0	0	•	0	0	0	0			+
POLY 08	0.14mm	104/2113	10	4,28	•	•	•	•	0	O	•	c	ŀ	1	1+
POLY 06	0.13mm	2×1080	6	#17# #17#	0	0	0	0	0	0	(C)	•		+	4
POLY 07	0.13mm	2116	3	4.23	0	0	•	0	0	0	C	9			
POLY 08	ů.16mm	106/2110	켪	4.23	•	•	0	0	0	C	•	C	1		
POLY 08	0.16mm	+080/2113	12	4.28	•	0	a	9	Ç	0	0	C	ì		ı
POLY 10	0.18mm	242113	90	4.34	0	0	0	•	•	c	P				1
POLY 11	0.18mm	7828	=	4.48	0	0	•	•	0	0	0	0		ı	-
POLY 12	D.21mm	2113/2116	4	177	•	0	С	-6	0	0	4	C	1		į
POLY 13	0.21mm	2×211B	94	4.48	•	С	0	4	0	ŀC	• 4	00	+		
POLY 14	0.25mm	252118	3	4.21	•	C	•	•	•	•		•	-		ŀ
POLY 16	0.36-л ш	7628/1080	42	4.62	•	•	¢	•	0	0	•	0	- 1	1	
POLY 16	0.26тм	2×1080/2118	2	4 18	9	0	0	•	•	• @	C	0	+	1/2	
POLY 17	0.31mm	2×1050/7629	43	4.42	•	•	0	9	•	•	•	C	+	+	
POLY 18	0.32mm	7828/2118		4.48	•	•	•	•	Ю	0	0	•	ı	- 1	1
POLY 19	0.37mm	2x7428	38	4.86	0	•	•	•	3	0	•	•	+	ı	ı
POLY 20	0.37mm	2×2113/7628	9	4.48	•	•	•	•	0	•	0	0	+		ı
POLY 21	0.43mm	2x2116/7628	=	# 11	•	•	•	•	0	0	0	0			1
POLY 22	GA3HH	2×7628/1080	Ŧ	4.60	•	•	•	•	0	0	0	•	+	ſ	ı
POLY 23	0.48mm	2×7028/2118	9	4.63	•	•	•	•	0	0	•	•	+	ı	1
POLY 24	0.51mm	2×10BD/2×762B	42	4.67	•	ø	0	•	•	•	0	0	ł	+	ı
POLY 24	0.53ம்ம	3x7428	13	4.86	•	•	•	0	0	•	•	•	1	1	ı
POLY 24	0.64mm	Zx2114/2x7525	ę	4.48	•	•	(3)	0	0	•	•	0	+		1
POLY 27	0.61mm	3x762B/108D	42	4.67	•	•	•	0	0	0	•	•	1	1	,
POLY 28	0.74mm	4x7628	30	4.08	9	9	•	•	0	c	•	0	+	ı	
PDLY 29	0.74mm	2K2113/3k7028	#	4.57	•	0	0	0	C	•	C	C	+		ı
POLY 30	0 ժետու	4x7828/1090	9	4.63	•	•	0	•	0	0	(1)	0	+		
POLY 31	1.52mm	8x7423	두	4.60	0	•	0	•	0	0	0	•	4	ŀ	1
								Γ							
				0	Đ	0	•	_ &							
				1	•	7 - 7 - 10	•								

Table 4-5 Polyimide Copper Clad Laminate Construction Selection Guide




Figure 4-2 Designer / end user materials selection map

1

- "L41" This grade is similar to L40 except that the resin chemistry may be altered. The applications are similar but higher operating temperature limits are possible.
 The T_g is specified as above 250°C.
- "L30" Woven "E" grass fabric impregnated with BT resin. This resin is a mixture of bismaleimides and triazine. Its uses are similar to those for L25. The Tg is normally from 165 to 180°C. Hot strength retention should not be confused with flame resistance. Hot strength retention allows the board to operate at higher temperatures without losing electrical and mechanical properties. Flame resistance implies self-extinguishing properties.

4.3.7 2 Dielectric Thickness The next four numbers of the code (1500) designates the nominal dielectric thickness.

The nominal base thickness is identified by four digits that indicate the thickness of the base material in thousandths of a millimeter (i.e., 1500 represents a nominal base thickness of 1.5 mm). When English units are specified, the four digits indicate thickness in ten-thousandths of an inch [i.e., 0590 = 0.059 in]. The overall nominal thickness does not include the metal cladding. The nominal thickness (i.e., 1500) stands alone with no tolerance. The drawing title block tolerance of three dramal places does not apply. Later in the code is a designation that applies a tolerance to the nominal thickness per industry standards. Whatever nominal thickness (typically 1.5 mm) is required, the corresponding number is inserted.

4.3.7.2 Copper Foil Designation The type and nominal weight of the copper foil cladding is identified by the next five characters of the code (i.e., CI/CI). The first and fourth characters of this designator will consist of the following letters to indicate the type of copper foil cladding.

- A Copper, rolled, wrought (IPC MF 150, Class 5).
- B Copper, rolled (treated).
- C Copper, drum side out, electrodeposited (IPC-MF-150, Class 1).
- D Copper, drum side out, (double treated) electrodeposited.
- G Copper, high ductility electrodeposited (IPC-MF-150), Class 2).
- H Copper, high temperature elongation (IPC-MF-150, Class 3).
- J Copper, annealed electrodeposited (IPC MF-150, Class 4).
- K Copper, light cold rolled wrought (IPC-MF-150, Class 6).
- L Copper, annealed wrought (IPC-MF-150, Class 7).
- O Unclad
- M Copper, as rolled wrought-low temperature (IPC-MF-150, Class 8).

- N Nickel
- U Aluminum
- V Copper-Invar-Copper (IPC-CF-152)

Type C or H copper foil claddings are most often used.

The second and the fifth characters of this designator will indicate the nominal copper foil weight in ounces per square foot (oz/ft²). The two indicators, which are separated by a slash (third character), will use the actual numbers for copper foil 1 oz/ft² or over, and the following let ters for copper foil under 1 oz/ft²

- $E = 0.125 \text{ oz/} R^2$
- Q 0.25 oz/fr²
- $T = 0.375 \text{ oz/ft}^2$
- H 0.50 oz/ft²
- $M = 0.75 \text{ oz/ft}^2$
- O Unclad
- X For any weight or thickness not expressed (e.g., 10 oz. copper foil) by a single digit designator. For example, "C1/C1" designates 1 oz/ft copper, drum side out, on one side and 1 oz/ft copper drum side out, on the other side. The slash should be considered to be the base laminate.

Base materials that are unclad on both sides would be designated 00/00.

Thus designation does not mean the total amount of copper that should be on the surface after processing (see IPC-2221).

Copper foils can be specified in foil weights from 0.125 to 7 oz/ft².

"CX/00" is the requirement for single-sided boards.

"CX/CX" is the requirement for double-sided boards.

- 4.3.7.4 Pit Designation The thirteenth character ("A") in the material specification code denotes the class of pits and dents allowed in the copper foil. Class of foil indentations is determined by the total amount and individual length of the pits and dents. A "pit" is a disruption or void in the surface of the copper, and must be within the limitations allowed by the applicable procurement document. A "dent" is a depression in the surface of the base laminate, and under pressure during lamination, the dent is transferred to the surface of the copper. There are five allowable designations: "A", "B", "C", "D", and "X" (see IPC-4101).
- "A" designation [29 points per 300 mm x 300 mm area]
 is adequate down to 0.25 mm conductors and spaces.
- "B" designation [5 points per 300 mm x 300 mm area] should be considered below 0.25 mm conductors and spaces.

- "C" designation [17 points per 300 mm x 300 mm area].
- "D" designation [0 points per 300 mm x 300 mm area].
- "X" designation" shall be as agreed between user and supplier (IPC-4101).
- **4.3 7.5 Thickness Class Tolerance Designation** The designation "I" is a thickness class tolerance specification for the base laminate (see table below).
- If the board is going to mount on standoffs and/or the thickness is of no importance, Class 1 should be specified
- If the board is required to plug into an edge connector, Class 2 or even Class 3 should be considered. The finished board thickness includes the nominal laminate thickness and the class tolerance, plus all the additional plating thicknesses added together.
- 4.3.7.6 Bow and Twist Designation The final character in the material specification code (for the laminate material only, not the final etched board) is a "bow and twist" specification per the following. These values apply only so sheet sizes as manufactured, and to cut pieces having either dimension no less than 460 mm.
- For nomina, thicknesses not shown, the bow or twist for the next lower thickness shown applies.
- A board that has both dimensions less than 460 mm generally requires an "A" specificanon.
- A board that has both dimensions greater than 460 mm requires a "B" specification.
- Boards that have one dimension less than 460 mm and the other greater than 460 mm, and have gold fingers on the long dimension, require a "B" specification.
- Class "X" indicates no bow or twist requirement and may be used only for single-sided boards. But in the case of bow, the percentage is stated in terms of the lateral dimension (length or width); in the case of twist, the percentage is stated in terms of the dimension from one corner to the diagonally opposite corner.

If the specification does not call out any class tolerances, the loosest requirements are assumed.

- 4.4 Conductive Materials Conductive materials shall be in accordance with the generic standard IPC-2221
- 4.5 Organic Protective Contings Organic protective coatings shall be in accordance with the generic standard IPC-2221
- 4.6 Markings and Legends Marking and legends shall be in accordance with the generic standard IPC-2221

5.0 MECHANICAL/PHYSICAL PROPERTIES

5.1 Fabrication Requirements Fabrication requirements shall be in accordance with the generic standard IPC-2221 and as follows.

Typical maximum fabrication panel size limits for board processing equipment are summarized in Table 5-1

- **5-2 Product/Board Configuration** Product/board configuration shall be in accordance with the generic standard IPC-2221 and as follows.
- **5.2.1 Board Geometries** The following are considerations to be taken into account during the design of a printed board.
- **5.2.1.1 Borders and Spacing** Borders and margins are commonly employed by the printed board fabricator to provide room for tooling features and other process control features (see Figure 5-1).

The size of such borders is usually in the range of 10 to 40 mm. This is determined by also taking into account an optimum number of boards per panel, obtaining optimum plating across the panel (especially important for high-density/fine line boards), etc.

When the printed boards are made using a print-and-etch procedure the border size may depend on the type of printed boards tend to have smaller borders; multilayer printed boards tend to have wider borders. Also, the size of the borders need not be the same on all four sides of the panel

The margins between boards on a panel also have to accommodate the panel/board shearing, blanking and routing operations. Thus, their size is commonly chosen to be either 4.8, 5.0 and 6.5 mm or the nearest dimension suitable to maintain the board features on the basic processing grid.

- 6.2.1.2 Dimensional Aspect Ratio Board length to width relationships should be kept as similar as possible. Long narrow boards or unusually-shaped boards lead to excessive bowing/twisting. Dimensional instability, and associated problems at all stages of fabrication, assembly, test and system fixturing become factors in determining final board size.
- **6.2.2 Support** Adequate mechanical support should be provided typically for at least two opposite edges of a printed wiring assembly. The location and method of support shall be such as to minimize shock and/or vibration to a level that will protect against fracturing or loosening of conductor foil, or breaking of the components or component leads as a result of flexing the printed board assembly within the tolerance of the applicable specification.
- **5.3 Assembly Requirements** Assembly requirements shall be in accordance with the generic standard IPC 2221 and as follows:

Table 5-1 Panel Size to Manufacturing Operation Relationships

Operation	Typical Maximum Panel Size
Dril	460 mm x 610 mm
Scrub, deburr, and most conveyorized finishing equipment	610 mm x open
Plating equipment	Custom sized, check with fabricator
Exposure equipment	610 mm x 610 mm
Routing equipment	460 mm x 610 mm
Screening equipment	510 mm x 760 mm
Bare board test	460 mm x 460mm
Laminaling press size (based on 610 mm x 760 mm press with 50 mm open area on plated edges)	510 mm x 660 mm
Solder coaling	460 mm x 610 mm




Figure 5-1 Panel borders

5.3.1 Assembly and Test Palletization of parts is a standard process in many instances for both test and assembly. This can be achieved using a number of different techniques. These include simple scoring, a combination of routing and scoring, and a combination of routing plus breakaway.

Scoring is the machining of a shallow, precise V-groove into the top and bottom surfaces of the laminate. It is generally accomplished using CNC equipment. As scoring allows the removal of rails and individual parts from a pallet, positional accuracy is critical. See Table 5-2 and Figure 5-2 for some standard scoring parameters.




Figure 5-2 Scoring parameters

Table 5-2 Standard Scoring Parameters

Letter	Title	Definition	Attainable Tolerances
Α	Web	The material remaining between the two (2) 'V' scores on a plane perpendicular to the printed board surface	± 60 µm
В	Centrality	The distance the center of a web is offset from true center within the printed board.	± 80 μm
C	Blade offset	The distance the top and bottom scoring blades are offset from one another	± 80 µm
D	Score width	The width of a score line at the surface of the printed	± 80 µm
E	Cutter angle	The total angle of a scoring blade.	± 2°
F	Keep out area	The area, expressed from nominal score line placement, that no features should be placed within.	D/2 + All registration
G	Printed board thickness	Overall printed board thickness to be scored.	Per PC standards
Н	Trueness/ Position	The tolerance of two or more score fines on one side of the printed board. Measured from nominal, squareness and actual position.	± 80 µm cumulative

Routing is the process of profiling a pallet or printed board to the correct dimension using a cutting bit. This can be performed either by the use of a pin router and template, or a CNC routing machine

Frequently a combination of routing and scoring is used, where both paliet and printed board are routed, leaving a small connection bridge. This bridge is then scored to facilitate removal following test and assembly.

The fina, method involves the use of routing and drilled breakaway tabs. Instead of scoring, a series of boles are drilled in the tab to facilitate removal. (See Figure 5-3.)




Figure 5-3 Breekaway taba

6.4 Dimensioning Systems Dimensioning systems shall be in accordance with the generic standard IPC-2221 and as follows.

5.4.1 Grid Systems When manually designing printed boards, grid systems are used to locate components, plated-through holes, conductor patterns, and other features of the printed board and its assembly so they need not be individually dimensioned. When printed board features are required to be off a grid, they shall be individually dimensioned and toleranced on the master drawing.

Grid systems are always basic and have no tolerance, and therefore all features located on a grid shall be toleranced elsewhere on the master drawing. Grid systems shall be located with respect to a minimum of two printed board datums.

The grid increment shall be specified on the master drawing. The choice of grid increment is based on the component terminal location for through-hole components, and on the component center for surface mount components.

Typical grid increments are multiples of 0.13 mm for through-hole components, and 0.05 mm for surface mount components.

5.4.2 Profiles, Cutouts and Notchos It is recommended that the number of cutouts and notches on the printed board be kept to a minimum in order to decrease the amount of time and effort necessary to fabricate them. This ultimately will help to minimize end-product printed board cost.

All such cutouts and notches must not interfere with the fabrication of other printed board/assembly features, such as the placing of edge-board contacts. The edges of internal cutouts shall be considered as external board edges and meet all requirements for hole and conductors to edge clearance (see 10.1.1). On multilayer printed boards the location of lands, clearances, ground planes and other conductive patient features must also be considered.

For printed board shape routing, it is recommended that the cutouts and notches allow for a minimum of a 1.5 mm radius on internal corners (assuming that a 3 mm diameter router bit is used). Although a minimum internal radius of 0.75 mm can be obtained with a 1.5 mm diameter router bit, this requirement should be avoided as router efficiency and accuracy decreases substantially when smaller router bits are used. Recommended tolerances for the location and profile of cutouts and notches are shown in Table 5-3; however, the tolerances specified on the printed board drawing shall accommodate the dimensions and tolerances of the mating part.

Table 5-3 Tolerance of Profiles, Cutouts, Notches, and Keying Slots, as Machined, mm

Tolerances to be applied to profile of a surface:	Level A ¹	Level B	Level C
Profile feature	0 25	0.20	0.15
Location where greatest basic location dimension is less than 300.0	0.30	0.25	0.20
Location where greatest basic location dimension is greater than 300.0	0 35	0.30	0.25

For definition of producibility level, see IPC-2221.

8.0 ELECTRICAL PROPERTIES

Electrical properties shall be in accordance with the generic standard IPC 2221

7.0 THERMAL MANAGEMENT

Thermal management shall be in accordance with the generic standard IPC-2221

8.0 COMPONENT AND ASSEMBLY ISSUES

Component assembly issues shall be in accordance with the generic standard IPC-2221 and as follows.

- 8.1 General Attachment Requirements In addition to the general attachment requirements outlined in the generic standard IPC-2221, the following shall apply:
- 8.1.1 Attachment of Wires/Leads to Terminals For cases in which more than one wire is attached to a terminal, the largest diameter wire should be mounted to the bottom-most post for ease of removal and repair. In general, no more than three attachments should be made to each section of a turret or bifurcated terminal. As an exception, bus bar terminals may hold more than three wires or leads per section when specifically designed to hold more.
- 8 1.2 Board Extractors Board extractors or handles are used to provide a convenient means of extracting the printed board from its mating connector. They are generally used where the amount of force makes it difficult to safely remove the board without damage to the electrical components or to the person removing the board.

Board extractors are commercially available and come in a variety of shapes and sizes.

Extractors are usually of the camming type and are mounted to the corners of the board. They provide a mechanical advantage for disengaging the connectors and a convenient place to grasp the board during removal.

Board extractors may be incorporated into the design of the board, or may require separate conditions in the printed board assembly. When board extractors are a part of the design, adequate reinforcement shall be used to properly allow the extracting action to remove the board from its connected assembly in the backplane (see Figure 8-1).

When board extractors are not a part of the printed board assembly, an extractor of the gripping variety may be used (see Figure 8-2). They grip the board in a particular area, which shall be kept free of components and circuitry. If a hook-type board extractor is used, where a hook passes through hores in the printed board, and then pulls the board out, special grommets should be used to reinforce the hole structure to avoid board crazing or cracking.




Figure 8-1 Permanent board extractor




Figure 8-2 External board extractor

9.0 HOLE/INTERCONNECTIONS

- 9.1 General Requirements for Lands with Holes General requirements for lands with holes shall be in accordance with the generic standard IPC-2221 and as follows.
- 9.1.1 Land Requirements When eye, ets or standoff terminals are used, the lands on external layers shall be so designed as to have a minimum a diameter of at least 0.5 mm greater than the maximum diameter of the projection of the eyelet of solder terminal flange.
- 9.1.2 Thermal Relief in Conductor Planes The relationship between the hole size, land and web area is critical Typically, divide 60% of the minimum land area diameter by the number of webs desired to obtain the width of each web in accordance with the following example:

A. Land Size Calculation

Maximum hote size = 1.0 mm

Annular ring $= 2 \times 0.05 \text{ mm}$ = 0.10 mm

Fabrication allowance = 0.25 mm

Musimum land size = 1.0 mm + 0.10 mm + 0.25 mm= 1.35 mm diameter

B. Thermal Relief Calculation

Total thermal width = 60% of land size = 0.6×1.35 mm = 0.80 mm

C. Original Web Size Calculation

2-web width = 1/2 of total thermal width = 0.50 x 0.80 mm = 0.40 mm

3-web width = 1/3 of total thermal width = 0.33 x 0.80 mm = 0.27 mm

4-web width = 1/4 of total thermal width = 0.25 x 0.80 mm = 0.20 mm

If the actual and diameter chosen is greater than the minimum value calculated, the percentage difference between the and diameters must be subtracted from the total web width calculation, i.e.

Minimum land diameter = 1.35 mm

Actual land diameter = 1.70 mm

Percent difference = (1.70 - 1.35 mm)/1.35 mm = 25%

New total web width = total web width percent difference = 0.80 mm - 25% (0.80 mm) = 0.60 mm

D. Adjusted Web Size Calculation

2-web width = 1/2 of new total web width = $0.50 \times 0.60 \text{ mm}$

= 0.30 mm

3 web width = 1/3 of new total web width

 $= 0.33 \times 0.60 \text{ mm}$ = 0.20 mm

4-web width 1/4 of new total web width

= 0.25 x 0 60 mm

= 0.15 mm

Total cumulative copper web for all layers in any plated through hole should not exceed 4.0 mm for 1 oz copper or 2.0 mm for 2 oz copper.

The total of the thermal rehef cross-sectional area divided by the number of planes connected to the plated through hole shall not violate current carrying capacity requirements for a given hole.

If the individual web width violates the intended minimum conductor width it shall be specified on the master drawing.

9.1.3 Clearance Area in Planes Clearance area in planes shall be provided in accordance with Figure 9-1




Figure 9-1 Clearance area in planes, mm

9.1.3.1 Small Pitch Clearance Area in Planes A special precaution must be observed when routing high speed circuits and/or very small pitch devices. When routing small pitch devices and/or vias routed on small grids, designers must remain aware of factors relating to power/ground plane clearance areas. When the pitch is very small, designers must remain cognizant of the parrow foil web between clearance openings (see Figure 9-2). As the clearance area (diameter) is made larger, the foil web between cicarance areas becomes smaller. Designs having very small foil webs are less desirable because of their reduced current carrying capability, potential for increased voltage drop, higher EMI emissions, and reduced thermal dissipating characteristics. It is highly desirable for heat generating devices to be "heatsinked" down through via holes and dissipated across the surface of inner planes. For these reasons the foil web should be as large as possible and overlapping clearance areas in planes should be avoided. Use the following formula when dealing with small pitch devices and/or via holes, when routing on very small grids.




Figure 9-2 Foll web size

Typical example: Determine the desired width of foil web Ex. 0.20 mm Web

Total available area = pitch foil web = 1.25 0.20 mm = 1.05 mm

B=0.25 mm m.n. fabrication allowance per Table 9-1 of IPC 2221

Clearance area (diameter) = hole diameter (max.) + 2B = 0.35 mm + 2 (0.25 mm) = 0.35 mm + 0.50 mm = 0.85 mm

Note: Maximum clearance area (diameter) in the plane is calculated by using the formula above and must not exceed the total available area.

9 1.4 Nonfunctional Lands Nonfunctional lands should be included on internal layers for all plated-through holes. Nonfunctional lands need not be used where electrical clearance requirements do not permit, such as ground planes, voltage planes and thermal planes. For high layer count boards, greater than 10 layers, it is recommended to remove some of the nonfunctional lands in the vertical stack. Plated-through holes passing through internal conductive planes (ground, voltage, etc.) and thermal planes shall meet the same minimum spacing requirements as conductors on internal layers, and should meet the minimum spacing requirements of Figure 9-2.

9.1.5 Conductive Pattern Feature Location Tolerance. The presentation in Table 9-1 is for the tolerance to be applied to the nominal dimension chosen for the location of the lands connector contacts and conductors in relation to the datums. This tolerance includes tolerances for master pattern accuracy, material movement, layer registration and fixturing.

Table 9-1 Feature Location Tolerances (Landa, Conductor Pattern, etc.) (Diameter True Position)

Greatest Board/ X, Y Dimension	Level A	Level B	Level C
Up to 300 mm	0.30 mm	0.20 mm	0 10 mm
Up to 450 mm	0.35 mm	0 25 mm	0.15 mm
Up to 600 mm	0.40 mm	0.30 mm	0.20 mm

Note: Conductor patient registration may be expressed in terms of minimum annular ring violation, which establishes manufacturing registration.

9.2 Holes Holes shall be in accordance with the generic standard IPC-2221 and as follows:

9.2.1 Unsupported Holes

9.2.1.1 Diameter of Unsupported Holes When using the basic dimensioning system, holes shall be expressed in terms of maximum material (MMC) and least material condiction (LMC) limits. The diameter of an unsupported component hole shall be such that the MMC of the lead subtracted from the MMC of the hole provides a clearance between a minimum of 0.15 mm and a maximum of 0.5 mm. The number of different hole sizes shall be kept to a minimum. When flat ribbon leads are mounted through unsupported holes, the difference between the nominal diagonal of the lead and the inside diameter of the unsupported hole shall not exceed 0.5 mm and shall be not less than 0.15 mm.

9.2.1.2 Unsupported Hole Tolerance When using the basic dimensioning system, holes shall be expressed in terms of maximum material condition (MMC) and least material condition (LMC) limits. The bilateral tolerances shown in Table 9-2 are used to determine the MMC-LMC limit for the appropriate hole diameter; thus, a hole 1.0 \pm 0.05 mm would be expressed as 0.95.1.05 mm

Table 9-2 Minimum Unsupported Holes Tolerance Range (Difference between high and low hole size limits)

1	Hole Diameter	Level A	Level B	Level C
	0.1 - 0.8 mm	0.15 mm	0 10 mm	0 05 mm
1	0.81 - 1.6 mm	0.20 mm	0.15 mm	0 10 mm
	1.61 5.0 mm	0.30 mm	0 20 mm	0.15 mm

9.2.1.3 Eyelet Hole Diameter When eyelets are used, the diameter of holes in which eyelets are inserted shall not exceed the outside diameter of the barre, of the eyelet by

more than 0.15 mm. The relationships between maximum and minimum barrel diameters and wire diameters shall be as shown in Table 9-3

9.2.2 Plated-Through Holes The maximum and minimum plated-through hole diameters used to attach component leads or pins to the printed board shall be evaluated in accordance with Table 9-3. Both minimum and maximum leads shall be taken into consideration in evaluating the finished plated through hole requirements. If the lead is a ribbon lead, the minimum and maximum diagonal of a flat ribbon lead shall be considered. Table 9-3 shows the limits of the plated-through hole.

These limits shall be optimized so that manufacturability is enhanced to provide the most "beral tolerances allowable (see Figure 9-3).




Figure 9-3 Lead-to-hole clearance

Unless otherwise specified, the hole size shall be the fin-shed plated size after solder coating or final plating and fusing, if required. The hole size shall be specified on the master drawing. Plated-through holes used for functional interfactal connections shall not be used for the mounting of devices which put the plated-through hole in compression. Plated-through holes used for functional interfactal connections shall not be used for the mounting of eyelets, solder terminals, or nivets. Plated-through holes shall be used for all interfactal connections on multilayer boards. Type 3 through Type 6 (inclusive). Platings and coatings shall be in accordance with IPC 2221.

9.2.2.1 Aspect Ratio The aspect ratio of plated through holes plays an important part in the ability of the manufacturer to provide sufficient plating within the plated-through hole, as well as in the reliability of the PTH/PTV structure

(see IPC D-279) Table 9-4 provides information on the productionally of aspect ratios for various levels of complexity

9.2.2.2 Plated-Through Hole Tolerances When using the basic dimensioning system, plated-through holes—used to attach component leads or plas to the printed board should be expressed in terms of MMC and LMC limits. The bilateral tolerances shown in Table 9-5 are used to determine the MMC-LMC limit for the appropriate finished hole diameter. Thus, a hole 1.0 ± 0.05 mm would be expressed as 0.95-1.05 mm. When hole size is less than one-fourth the basic board thickness, the tolerance shall be increased by 0.05 mm.

8.2.2.3 Minimum Hole Sizes for Plated-Through Hole Vias In order to meet the performance requirements of the various classes of equipments, the plated-through hole size to board thickness aspect ratio for plated-through hole vias should be in accordance with Table 9-4. Table 9-6 provides information on the minimum drilled hole to be used in conjunction with various board thicknesses. The table reflects the three classes of equipment assuming that each class requires a slightly more severe environment, thus having to meet more stringent thermal cycling conditions (see IPC-D-279)

If a particular class requires more stringent cycling than shown in the table, the user may invoke the requirements of a larger drilled hole size.

Solder may fill the through hole or via if processed with fused tin-lead plate or solder coating. Partial filling at assembly can create stress concentrations affecting rehability. For drilled hole diameters 0.35 mm or less and aspect ratios of 4:1 or larger, the fabricator should mask or plug by a suitable method the plated through vias to prevent entry of solder.

The drilled hole size used for through hole vias shall be represented on the master drawing as the maximum plated-through hole dimension that assumes that the hole contains a minimum plating thickness. No minimum plated-through hole dimension should be specified since the through-hole via contains no component lead or pin and could theoretically be plated shut. Thus, a master drawing call out of 0.0-0.2 mm diameter reflects drilling a 0.25 mm hole that can contain a minimum plating of 0.025 mm to a maximum plating of 0.125 mm copper per side

In addition, Table 9-6 contains a letter code in each of the boxes. This letter code reflects the producibility level of complexity in each of the particular hole size to aspect ratios.

9.2.3 Etchback Etchback, when required, will reduce the annular ring support on internal layers of the board Therefore, this should be taken into account when specifying plated-through hole land size. However, the maximum.

Table 9-3 Plated-Through Hole Diameter to Lead Diameter Relationships

Lead Diameter	Level A	Level B	Level C
	No greater than 0.7 mm over minimum lead diameter	No greater than 0.7 mm over minimum lead diameter	No greater than 0.6 mm over minimum lead diameter
Minimum hole to maximum lead diameter	No less than 0.25 mm over maximum lead diameter	No less than 0.20 mm over maximum diameter	No less than 0.15 mm over maximum lead diameter

Table 9-4 Plated-Through Hole Aspect Ratio

	Level A	Level B	Lavel C
Aspect Ratios	≤5:1	6:1 to 8:1	9:1 and up

etchback allowed on the master drawing shall not be greater than the minimum design annular ring.

9.3 Drill Size Recommendations for Printed Boards Drill sizes as related to maximum board thickness are shown in Table 9-7. These drills may be used to drill unsupported or plated-through holes in rigid printed boards.

Although the designer rarely specifies the drilled hole size, these dimensions may be used in determining minimum annular ring calculations, or minimum land sizes.

Also shown in Table 9-7 are the maximum board thicknesses to which the various drill sizes should be applied. (Note: These dimensions are maximums. Thinner boards may be used to accommodate all drills shown within a drill set category.) Designers are encouraged to limit the number of drill selections to approximately 10 drill sizes per each printed board. Where possible a lesser number should be used, recognizing that the manufacturer needs certain drill sizes for tooling hole and other configurations. It is recommended that the designer select no more than one drill size from any given row in order to optimize drill size operation. The information in Table 9-7 is a suggested guideline based on the availability of existing manufacturing drills.

Table 9-7 Drill Size Recommendations Related to Maximum Board Thickness

Driff size (mm)	Maximum Board Thickness (mm), as drilled
⊴0 10	≲0 25
0.15-0.25	≤1 0
0.30-0.45	≤1 5
0.50-0.85	\$3.2
0 90-1.05	≤4 8
≤1 10	≤6.4

10.0 GENERAL CIRCUIT FEATURE REQUIREMENTS

10.1 Conductor Characteristics Conductor characteristics shall be in accordance with the generic standard IPC-2221 and as follows:

10.1.1 Edge Spacing Except for edge-board contacts, the minimum distance between conductive surfaces and the edge of the finished board, or a non-plated through hole, shall not be less than the minimum spacing specified in Table 6-1 of IPC-2221 plus 0.4 mm. Printed boards that slide into guides shall have a minimum external conductor to guide distance of 1.25 mm or minimum electrical clearance (see Table 6-1 of IPC-2221), whichever is greater Special design applications in areas such as high voltage, surface mount, and radio frequency (RF) technology may require variances to these requirements. Ground and heat sink planes may extend to the edge when required by design.

Table 9-5 Minimum Plated-Through Hole Diameter Tolerance Range, mm (Difference between high and low hole size limits)

	Level A	Level B	Level C
Hole Diameter	DB461 V		0.40
0 1 to 0.8	0.20	0 15	0 10
	0.30	0.20	0.10
0.8 to 1 6		0.20	0.20
>1 6 to 5.0	0.40	0.30	0.20

Table 9-6 Minimum Drilled Hole Size for Plated-Through Hole Visa

Board Thickness	Class 1	Class 2	Class 3
1 0 mm	Level C 0.15 mm	Level C 0.2 mm	Level C 0.25 mm
.0 mm to 1.6 mm	Level C 0.2 mm	Level C 0 25 mm	Level B 0.3 mm
1.6 mm to 2.0 mm	Level C 0.3 mm	Level B 0.4 mm	Level B 0.5 mm
>2 0 mm	Level B 0.4 mm	Level A 0.5 mm	Level A 0.6 mm

Note: If copper pleting thickness in hole is greater than 0.03 mm, hole size can be reduced by one class.

February 1998 IPC 2222

10 1 2 Balanced Conductors Whenever possible, to reduce bow and twist and to increase dimensional stability, conductors should be balanced within an individual layer. Conductor routing density should be spread throughout the board wherever possible, to avoid the need for special etching or plating thieves.

Plating thieves are added metallic areas which are nonfunctional within the finished board profile but allow uniform plating density, giving uniform plating thickness over the board surface.

The multilayer printed board structure should also be as balanced as possible providing equal layers of signal conductors and planes to eather side of the center of the multilayer construction.

10.1.3 Flush Conductors for Rotating or Sliding Contacts. When flush carcuits are required for application as mating contact surfaces, the degree of flushness shall meet the requirements of Table 10-1 Figure 10-1 (A and B) shows a typical flush circuit design.

Note. The level of flushness required is normally a function of factors related to the mating contact, such as contact size, shape, load, rotational force, surface friction, etc. It is recommended that the designer fully understand the dynamics of the mating contact system before establishing surface flushness requirements.

Table 10-1 Surface Flushness Requirements

Level A	Level B	Level C
As agreed between user	± 0.013 mm	± 0.005 mm
and supplier		




Figure 10-1A Typical flush circuit

10.1.4 Metallic Finishes for Flush Conductors Meta...c finishes for flush conductor contacts should be gold over nickel, or other suitable corrosion resistant, low contact resistance finish.

10.2 Land Characteristics Land characteristics shall be in accordance with the generic standard IPC 2221 and as follows:

10.2.1 Lands for Interfacial Connection Vias Lands for interfacial connections shall meet the requirements of 10.1

10.2.2 Offset Lands Lands, when used in conjunction with clinched leads, may be located adjacent to (not surrounding) the lead termination hole. The land shall be a sufficient distance from the hole to allow chipping of the part lead prior to unsoldering the part lead from the land.

10.2.3 Conductive Pattern Feature Location Tolerance The presentation in Table 9-1 is for the tolerance to be applied to the nominal dimension chosen for the location of the lands connector contacts and conductors in relation to the datums. This tolerance includes tolerances for master pattern accuracy, material movement, layer registration and fixturing. (See IPC-SM 782.)

10.2.4 Nonfunctional Lands See 9.1.4.

10.3 Large Conductive Areas Large conductive areas (Planes 3 mm wide or larger conductors) increase the likelihood for blistering, warping, or heat shielding during wave or reflow soldering.

Large areas that cover more than a 25.0 mm diameter may be broken up into a cross-hatched or similarly patterned area (see Figure 10-2). Modifications to large conductive areas shall not adversely impact the electrical characteristics or performance of the board. Large conductive areas should not be on the soider side of the board unless soider resist or similar is used.

External conductors that extend beyond a 25 0 mm drameter circle should contain etched areas that break upthe large conductive area, but retain the continuity and functionality of the conductor. If etched areas are not provided, other methods should be used to minimize blistering or bowing.

Large conductive areas should, if possible, be on the primary side of the board. If solder resist is employed over meltable metals, conductive areas wider than 1.3 mm shall not be employed under the solder resist coatings.

When a conductive area that extends beyond a 25.0 mm diameter is used on a internal layer, the conductive area




Figure 10-1B Surface flushness conditions




Figure 19-2 Cross-hatched large conductive layers with isothermal conductors

should be placed as near to the center or the board as possible, and should contain etched areas that will break up the large conductive area, but will retain the continuity and functionality of the conductor. When UL requirements are imposed, the area shall be within the limits approved by UL for the printed board manufacturer

11.0 DOCUMENTATION

Documentation shall be in accordance with the generic standard IPC-2221 and as follows.

11.1 Filled Holes Via holes designated to be filled by the design requirements shall be identified on the drawing.

11.2 Nonfunctional Holes Electrically nonfunctional supported holes should be identified as such on the fabrication or assembly drawing and do not need to meet the electrical connection requirement

12.0 QUALITY ASSURANCE

Quality Assurance shall be in accordance with the generic standard IPC-2221

NOTES

The following is an index of key subjects related to specific paragraph numbers in this standard. The index is organized alphabetically

А

Assembly and Test 5.3.1
Assembly Requirements 5.3
Assembly Types 1.6
Attachment Requirements 8.1

В

Balanced Conductors 10.1.2

Board Extractors 8.1.2

Board Geometries 5.2.1

Board Type 1.5.1

Borders and Spacing 5.2.1.1

Bow and Twist Designation 4.3.7.6

C

Circuit Feature Requirements 10.0
Classification of Products 1.5
Clearance Area in Planes 9.1.3
Component and Assembly Issues 8.0
Conductive Materials 4.4
Conductive Pattern Feature Location
Tolerance 9.1.5, 10.2.3
Conductor Characteristics 10.1
Copper Foil Designation 4.3.7.3

Ð

Diameter of Unsupported Holes 9 2.1 1
Dialectric Base Materials 4.2
Dialectric Thickness 4.3.7.2
Dialectric Thickness Measurement 4.3.1
Dialectric Thickness/Spacing 4.3.2
Dimensional Aspect Ratio 5.2.1.2
Dimensioning Systems 5.4
Documentation 11.0
Double-Clad Laminares 4.3.6
Dril. Size Recommendations 9.3

E

Edge Spacing 10.1 f
Electrical Properties 6.0
Electrical Requirements 4.3.4.4
Epoxy 4.3.4.1
Epoxy Laminates 4.2.1
Etchback 9.2.3
Eyelet Hole Diameter 9.2.1.3

Fabrication Requirements 5.1 Filled Holes 11.1 Flush Conductors 10.1.3

General Requirements 3.0
Glass Style 4.3.4.3
Grid Systems 5.4.1

PI

High-Temperature Laminates 4.2.2 High-Temperature Prepregs 4.3.4.2 Hole/Interconnections 9.0 Holes 9.2

i.

Laminate 4.2.4
Laminate Materials 4.3
Laminate Properties 4.3.3
Land Characteristics 10.2
Land Requirements 9.1.1
Lands for Interfacial Connection Vias 10.2.1
Lands with Holes 9.1
Large Conductive Areas 10.3

М

Markings and Legends 4.6

Material Selection 4.1

Materials 4.0

Mechanical Support 5.2.2

Mechanical/Physical Properties 5.0

Metallic Finishes for Flush Conductors 10.1.4

Minimum Hole Sizes for PTH Vias 9.2.2.3

N

Nonfunctional Holes 11.2 Nonfunctional Lands 9.1.4, 10.2.4

0

Offset Lands 10.2.2 Organic Protective Coatings 4.5

P

Pit Designation 4.3.7.4

Plated-Through Hole Tolerances 9.2.2.2

Plated-Through Holes 9.2.2

Prepreg 4.3.4

Product/Board Configuration 5.2

Profiles, Cutouts and Notches 5.4.2

q

Quality Assurance 12.0

R

Resin Content 4.3.3.2

S

Single-Clad Laminates 4.3.5 Small Pitch Clearance Area in Planes 9.1.3.1 Special Clad Materials 4.2.3

T

Thermal Management 7.0
Thermal Relief in Conductor Planes 9.1.2
Thickness Class Tolerance Designation 4.3.7.5
Thickness Tolerance 4.3.3.1
Typical Material Designation 4.3.7.1

.

Unsupported Hole Tolerance 9.2.1.2
Unsupported Holes 9.2.1

Wires/Leads Attachment to Terminals 8.1.1



ANSI/IPC-T-50 Terms and Definitions for

The purpose of this form is to keep SUBMITTOR INFORMATION:

nterconnecting and Packaging Electronic	Circuits
Definition Submission/Approval Sheet	

urrent with terms routinely used in	Name:
he industry and their definitions. Individuals or companies are	Company
nvited to comment. Please	City:
complete this form and return to:	State/Zip:
PC 2215 Sanders Road	
Northbrook, IL 60062-6135	Telephone:
Fax. 847 509 9798	Date:
☐ This is a NEW term and definition ☐ This is an ADDITION to an existing ☐ This is a CHANGE to an existing	g term and definition(s).
Term	Definition
	(I space not adequate, use reverse side or attach additiona, sheet(s)
	es:
	Office Use
IPC Office	Committee 2-30
	Date of Initial Review Comment Resolution:
Returned for Action:	
Revision Inclusion:	
	IEC Classification
Classification Code • Serial Number	
Terms and Definition Committee Fi	nal Approval Authorization:
	above term for release in the next revision.
Name:	Committee: IPC 2-30 Date

Technical Questions

The IPC staff will research your technical question and attempt to find an appropriate specification interpretation or technical response. Please send your technical query to the technical department via:

tel 847/509-9700 www.ipc.org fax 847/509-9798 e-mail: answers@inc.org

IPC World Wide Web Page www.ipc.org

Our home page provides access to information about upcoming events, publications and videos, membership, and industry activities and services. Visit soon and often.

IPC Technical Forums

IPC technical forums are opportunities to network on the Internet. It's the best way to get the help you need today! Over 2,500 people are already taking advantage of the excellent peer networking available through e-mail forums provided by IPC. Members use them to get timely, relevant answers to their technical questions. Contact KeachSasamori@ipc.org for details. Here are a few of the forums offered.

TechNet@ipc.org

TechNet forum is for discussion of issues related to printed circuit board design, assembly, manufacturing, comments or questions on IPC specifications, or other technical inquiries. IPC also uses TechNet to announce meetings, important technical issues, surveys, etc.

ComplianceNet@ipc.org

ComplianceNet forum covers environmental, safety and related regulations or issues.

DesignerCouncil@ipc.org

Designers Council forum covers information on upcoming IPC Designers Council activities as well as information, comments, and feedback on current designer issues, local chapter meetings, new chapters forming, and job opportunities. In addition, IPC can set up a mailing list for your individual Chapter so that your chapter can share information about upcoming meetings, events and issues related specifically to your chapter.

Gencam@ipc.org

Gencam deals with issues regarding the Gencam™ standards and specifications for Printed Circuit Board Layout and Design.

LeadFree@ipc.org

This forum acts as a peer interaction resource for staying on top of lead elimination activities worldwide and within IPC.

IPC_New_Releases@ipc.org

This is an announcement forum which subscribers can receive notice of new IPC publications, updates and standards.

ADMINISTERING YOUR SUBSCRIPTION STATUS:

All commands (such as subscribe and signoff) must be sent to listserv@ipc.org. Please DO NOT send any command to the mail list address, (i.e.<mail list>@ipc.org), as it would be distributed to all the subscribers.

Example for subscribing: To: LISTSERV@IPC.ORG

Example for signing off: To: LISTSERV@IPC.ORG

Subject:

Subject:

Message: subscribe TechNet Joseph H. Smith

Message: signoff DesignerCouncil

Please note you must send messages to the mail list address ONLY from the e-mail address to which you want to apply changes. In other words, if you want to sign off the mail list, you must send the signoff command from the address that you want removed from the mail list. Many participants find it helpful to signoff a list when travelling or on vacation and to resubscribe when back in the office.

How to post to a forum:

To send a message to all the people currently subscribed to the list, just send to <mail list>@ipc.org. Please note, use the mail list address that you want to reach in place of the <mail list> string in the above instructions.

Example:

To: TechNet@IPC.ORG Subject: <your subject> Message: <your message>

The associated e-mail message text will be distributed to everyone on the list, including the sender. Further information on how to access previous messages sent to the forums will be provided upon subscribing.

For more information, contact Keach Sasamori tel 847/790-5315 fax 847/504-2315

e-mail: sasako@ipc.org www.

www.ipc.org/html/forum.htm

Education and Training

IPC conducts local educational workshops and national conferences to help you better understand conventional and emerging technologies. Members receive discounts on registration fees. Visit www.ipc.org to see what programs are coming to your area.

IPC Certification Programs

IPC provides world-class training and certification programs based on several widely-used IPC standards, including the IPC-A-610, the J-STD-001, and the IPC-A-600. IPC-sponsored certification gives your company a competitive advantage and your workforce valuable recognition.

For more information on programs, contact Alexandra Curtis

tel 847/790-5377

fax 847/509-9798

e-mail: curtal@ipc.org

www.lpc.org

IPC Video Tapes and CD-ROMs

IPC video tapes and CD-ROMs can increase your industry know-how and on the job effectiveness. Members receive discounts on purchases.

For more information on IPC Video/CD Training, contact Mark Pritchard

tel 505/758-7937 ext. 202

fex 505/758-7938

e-mail: markp@ipcvideo.org

www.ipc.org

IPC Printed Circuits Expo®



IPC Printed Circuits Expo is the largest trade exhibition in North America devoted to the PWB manufacturing industry. Over 90 technical presentations make up this superior technical conference. Visit www.ipcprintedcircuitexpo.org for upcoming dates and information.

Exhibitor information:

Contact: Mary MacKinnon

Sales Manager tel 847/790-5386

e-mail: MaryMackinnon@ipc.org

Alicia Balonek

Exhibits Manager

fax 847/509-9798 e-mail: registration@ipc.org tel 847/790-5398

Registration information:

tel 847/790-5361

e-mail: AliciaBalonek@ipc.org

APEX® / IPC SMEMA Council **Electronics Assembly Process Exhibition & Conference**



APEX is the premier technical conference and exhibition dedicated entirely to the electronics assembly industry. Visit www.GoAPEX.org for upcoming dates and more information.

Exhibitor information:

Contact: Mary MacKinnon

tel 847/790-5386

e-mail: MaryMacKinnon@ipc.org

Registration information:

tel 847/790-5360 fax 847/509-9798

e-mail: goapex@ipc.org

How to Get Involved

The first step is to join IPC. An application for membership can be found in the back of this publication. Once you become a member, the opportunities to enhance your competitiveness are vast. Join a technical committee and learn from our industry's best while you help develop the standards for our industry. Participate in market research programs which forecast the future of our industry. Participate in Capitol Hill Day and lobby your Congressmen and Senators for better industry support. Pick from a wide variety of educational opportunities: workshops, tutorials, and conferences. More up-to-date details on IPC opportunities can be found on our web page; www.ipc.org.

For information on how to get involved, contact:

Jeanette Fertiman, Membership Director

tel 847/790-5309

fax 847/509-9798

e-mail: JeanetteFerdman@ipc.org

www.ipc.org



or not-for-profit organization.)

Application for Site Membership

Thank you for your decision to join IPC members on the "Intelligent Path to Competitiveness"! IPC Membership is **site specific**, which means that IPC member benefits are available to all individuals employed at the site designated on the other side of this application.

To help IPC serve your member site in the most efficient manner possible, please tell us what your facility does by choosing the most appropriate member category. (Check one box only.)

☐ Independent Printed Board M	anufacturers						
This facility manufactures and sells interconnection products on the me	to other companies, printed wiring						
One-sided and two-sided rigid printed boards	 Multilayer printed boards ☐ Flexible printed boards 	Other interconnections					
Name of Chief Executive Officer/President							
Independent Electronic Assen	ably EMSI Companies						
This facility assembles printed wiring products for sale.	ng boards, on a contract basis, and	may offer other electronic interconnection					
Name of Chief Executive Officer/Pr	resident						
	r manufactures printed wiring board anufacture and sell.	Captive Manufacturers of PCBs/PCAs					
☐ Industry Suppliers							
This facility supplies raw materials, electronic interconnection products		used in the manufacture or assembly of					
What products do you supply?							
Government Agencies/Acader	mic Technical Liaisons						
We are representatives of a govern concerned with design, research, a		echnical institute who are directly nection devices. (Must be a non-profit					



2215 Sanders Road, Morthbrewk, N. 60862-6135 Tel 847.509.9700 Fex 847.509.9798 www.jcc.org